## beecroft house 4

no.38b lot 2 malton road beecroft nsw architectural list:

cover page, site plan, basix and roof plan page 01

floor plans, elevation & sections page 02

1. FALLS, SLIPS, TRIPS a) WORKING AT HEIGHTS

DURING CONSTRUCTION Wherever possible, components for this building should be prefabricated off-site or at ground level to minimise the risk of workers falling more than two metres. However, construction of this building will require workers to be working at heights where a fall in excess of two metres is possible and injury is likely to result from such a fall. The builder should provide a suitable barrier wherever

DURING OPERATION OR MAINTENANCE For houses or other low-rise buildings where scaffolding is appropriate:
Cleaning and maintenance of windows, walls, roof or other
components of this building will require persons to be situated
where a fall from a height in excess of two metres is possible. Where

this type of activity is required, scaffolding, ladders or trestles should be used in accordance with relevant codes of practice, regulations or legislation. For buildings where scaffold, ladders, trestles are not appropriate Cleaning and maintenance of windows, walls, roof or other components of this building will require persons to be situated where a fall from a height in excess of two metres is possible. Where this type of activity is required, scaffolding, fall barriers or Personal Protective Equipment (PPE) should be used in accordance with relevant codes of practice, regulations or legislation.

FLOOR FINISHES Specified If finishes have been specified by designer, these have been selected to minimise the risk of floors and payed areas becoming slippery when wet or when walked on with wet shoes/feet. Any changes to the specified finish should be made in consultation with the designer or, if this is not practical, surfaces with an equivalent or better slip resistance should be chosen. FLOOR FINISHES By Owner

b) SLIPPERY OR UNEVEN SURFACES

If designer has not not been involved in the selection of surface finishes, the owner is responsible for the selection of surface finishes in the pedestrian trafficable areas of this building. Surfaces should be selected in accordance with AS HB 197:1999 and AS/NZ STEPS, LOOSE OBJECTS AND UNEVEN SURFACES Due to design restrictions for this building, steps and/or ramps are included in the building which may be a hazard to workers carrying

both visual and tactile warning during construction, maintenance, demolition and at all times when the building operates as a Building owners and occupiers should monitor the pedestrian access ways and in particular access to areas where maintenance is routinely carried out to ensure that surfaces have not moved or cracked so that they become uneven and present a trip hazard

cause a slip or trip hazard should be cleaned or removed from construction, maintenance or demolition to reduce the risk of trips and falls in the workplace. Materials for construction or maintenance should be stored in designated areas away from

2. FALLING OBJECTS LOOSE MATERIALS OR SMALL OBJECTS Construction, maintenance or demolition work on or around this building is likely to involve persons working above ground level or above floor levels. Where this occurs one or more of the following measures should be taken to avoid objects falling from the area

Prevent or restrict access to areas below where the work is being carried out. 2. Provide toeboards to scaffolding or work platforms.
3. Provide protective structure below the work area.
4. Ensure that all persons below the work area have Personal

where the work is being carried out onto persons below.

During construction, renovation or demolition of this building, parts of the structure including fabricated steelwork, heavy panels and many other components will remain standing prior to or after supporting parts are in place. Contractors should ensure that temporary bracing may injure persons in the area is a possibility

maintenance or demolition presents a risk of falling objects. Contractors should ensure that appropriate lifting devices are used, that loads are properly secured and that access to areas below the

3. TRAFFIC MANAGEMENT For building on a major road, narrow road or steeply sloping road: Parking of vehicles or loading/unloading of vehicles on this roadway may cause a traffic hazard. During construction, maintenance or demolition of this building designated parking for workers and loading areas should be provided. Trained traffic management personnel should be responsible for the supervision of these areas. For building where on-site loading/unloading is restricted:

Construction of this building will require loading and unloading of materials on the roadway. Deliveries should be well planned to avoid congestion of loading areas and trained traffic management personnel should be used to supervise loading/unloading areas. For all buildings:
Busy construction and demolition sites present a risk of collision where management plan supervised by trained traffic management

personnel should be adopted for the work site. 4. SERVICES

Rupture of services during excavation or other activity creates a variety of risks including release of hazardous material. Existing identified on the plans but the exact location and extent of SENGES-may vary from that indicated. Services should be located using an appropriate service (such as Dial Before You Dig), appropriate excavation practice should be used and, when Locations with underground power: Underground power lines MAY be located in or around this site. All underground power lines must be disconnected or carefully located and adequate warning signs used prior to any construction, maintenance or demolition commencin Locations with overhead power lines: Overhead power lines MAY be near or on this site. These pose a risk of electrocution if struck or approached by lifting devices or other plant and persons working above ground level. Where there is a danger of this occurring, power lines should be, where practical disconnected or relocated. Where this is not practical adequate

warning in the form of bright coloured tape or signage should be

5. MANUAL TASKS Components within this design with a mass in excess of 25kg should be lifted by two or more workers or by mechanical lifting device. Where this is not practical, suppliers or fabricators should All material packaging, building and maintenance components practical all items should be stored on site in a way which ninimises bending before lifting. Advice should be provided o Construction, maintenance and demolition of this building will require the use of portable tools and equipment. These should be specifications and not used where faulty or (in the case of electrical equipment) not carrying a current electrical safety t All safety guards or devices should be regularly checked and Personal Protective Equipment should be used in accordance

safety notes

6. HAZARDOUS SUBSTANCES

For alterations to a building constructed prior to 1990: If this existing building was constructed prior to: 1990 – it therefore may contain asbestos 1986 – it therefore is likely to contain asbestos either in cladding material or in fire retardant insulation material. In either case, the builder should check and, if necessary, take appropriate action before demolishing, cutting, sanding, drilling or otherwise disturbing the existing structure. POWDERED MATERIALS Many materials used in the construction of this building can cause harm if inholed in powdered form. Persons working on or in the building during construction, operational maintenance or demolition should ensure good ventilation and wear Personal Protective

Equipment including protection against inhalation while using powdered material or when sanding, drilling, cutting or otherwise TREATED TIMBER The design of this building may include provision for the inclusion of

treated timber within the structure. Dust or fumes from this material can be harmful. Persons working on or in the building during construction, operational maintenance or demolition should ensure good ventilation and wear Personal Protective Equipment including protection against inhalation of harmful material when sanding, drilling, cutting or using treated timber in any way that may cause harmful material to be released. Do not burn treated timber.

VOLATILE ORGANIC COMPOUNDS Many types of glue, solvents, spray packs, paints, varnishes and some cleaning materials and disinfectants have dangerous emissions. Areas where these are used should be kept well ventilated while the material is being used and for a period after installation. Personal Protective Equipment may also be required. The manufacturer?s recommendations for use must be carefully

SYNTHETIC MINERAL FIBRE Fibreglass, rockwool, ceramic and other material used for thermal or sound insulation may contain synthetic mineral fibre which may be harmful if inhaled or if it comes in contact with the skin, eyes or other sensitive parts or the body. Personal Protective Equipment including protection against inhalation of harmful material should be used when

TIMBER FLOORS This building may contain timber floors which have an applied finish Areas where finishes are applied should be kept well ventilated during sanding and application and for a period after installation. Persona Protective Equipment may also be required. The manufacturer?s recommendations for use must be carefully considered at all times

7. CONFINED SPACES EXCAVATION

Construction of this building and some maintenance on the building will require excavation and installation of items within excavations. Where practical, installation should be carried out using methods which do not require workers to enter the excavation. Where this is not practical, adequate support for the signs and barriers to prevent accidental or unauthorised access t ENCLOSED SPACES

For buildings with enclosed spaces where maintenance or other access may be required:
Enclosed spaces within this building may present a risk to persons entering for construction, maintenance or any other purpose. The design documentation calls for warning signs and barriers to unauthorised access. These should be maintained throughout the life of the building. Where workers are required to enter enclosed spaces, air testing equipment and Personal Protective Equipment should be provided. SMALL SPACES

For buildings with small spaces where maintenance or other access Some small spaces within this building will require access by construction or maintenance workers. The design documentation calls for warning signs and barriers to unauthorised access. These should be maintained throughout the life of the building. Where workers are required to enter small spaces they should be scheduled so that access is for short periods. Manual lifting and

8. PUBLIC ACCESS Public access to construction and demolition sites and to areas under maintenance causes risk to workers and public. Warning signs and secure barriers to unauthorised access should be

materials are present they should be secured when not fully

9. OPERATIONAL USE OF BUILDING RESIDENTIAL BUILDINGS This building has been designed as a residential building. If it, at a later date, it is used or intended to be used as a workplace, the provisions of the Work Health and Safety Act 2011 or subsequent

NON-RESIDENTIAL BUILDINGS For non-residential buildings where the end-use has not been This building has been designed to requirements of the classification identified on the drawings. The specific use of the building is not known at the time of the design and a further assessment of the workplace health and safety issues should be undertaken at the time of fit-out for the end-user.

For non-residential buildings where the end-use is known: This building has been designed for the specific use as identified on the drawings. Where a change of use occurs at a later date a further assessment of the workplace health and safety issues 10.0THER HIGH RISK ACTIVITY All electrical work should be carried out in accordance with Code of Practice: Managing Electrical Risks at the Workplace, AS/NZ 3012and all licensing requirements. All work using Plant should be carried out in accordance with Code of Practice: Managing Risks of Plant at the Workplace. All work should be carried out in accordance with Code of Practice: Managing Noise and Preventing Hearing Loss at Work.

Due to the history of serious incidents it is recommended that

particular care be exercised when undertaking work involving steel construction and concrete placement. All the above applies.

MALTON

RIDGE R.L. 132.56 GUTTER R.L. 131.29 ⁄38b DP1226564 existing stormwater pits and easement see building envelope 32 side setback to to wa**ll** 3635mm non s**l**ip garde proposed retaining wall new dwellina 900mm side setback to drainage easement  $\infty$ ယ 2 location. Concrete waste and storage bin to be located VER. 133.5 ္က်င္တာ ယ BIDGE 2g existing co 5 3.451 (A) RIGHT OF ACCESS & EASEMEN FOR SERVICES VARIABLE WIDTH (D.F (B) EASEMENT TO DRAIN WATER VARIABLE WIDTH (D.P. 1226564) (C) EASEMENT TO DRAIN WATER 1 1 WIDE & VARIABLE WIDTH (D.P. 122656 existing concrete driveway (D) RESTRICTION ON THE USE OF LAND (R.D.A.) (D.P. 1226564) (E) RESTRICTION ON THE USE OF LAND (A.P.Z.) (D.P. 1226564) (F) EASEMENT FOR DRAINAGE 1.525 WIDE (A709196) 3.351 / existing powerpole existing right of access >, CONC. entry and exit

5.31 12.945 2386m<sup>2</sup> U  $\infty$ 6 9 A.P.Z. 32 D <u>.</u>D  $\infty$ 0 ယ MALTON ROAD

overall site plan.

2

5

 $\infty$ 

0

datum location

winter sun path

458

0

129.5

Decetion of u/ground rainwater tank

Lot 3

38a

DP1226564

2412m<sup>2</sup>

see hydraulic engineers details

wa**ll** 2370mm

non slip garden steps

metre high stepped

side setback to single storev

retaining wall

garage wa**ll** 1050mm

part site/site analysis plan. (scale 1:250)

bushfire prone site BAL 29

bushfire prone site BAL 29

4A toilets flushing system

4A taps in the kitchen.

 3000 litres rainwater tank • tanks must collect at least from 280m2 of the roof • tanks must be connected to all toilets

 at least one outdoor tap. tank must be connected to clothes washer

Thermal

alternative

commitments • refer to certificate for all window and glazed door specifications

 Hot water system must be gas instant 6 stars commitments • Heating EER 3.5-4.0 and cooling system must be 3 phase EER 3.0-3.5 with cell

• Exhaust systems to all bathrooms, kitchen and laundry.

• compact fluoros and LED's to all bedrooms/study and bathrooms/toilets

 natural lighting to at least four bathrooms induction cooktop and electric oven.

well ventilated frigerator space

One fixed outdoor clothes line

## basix detail

certificate no: 1132496S date: 14th December 2020 summary only please refer to basix certificate for exact


## general notes and specifications (applies to all pages)

- It is the responsibility of the builder/owner to check & verify all all boundaries, dimensions & building details prior to construction to satisfy him/ the work can be carried out as required. Any discrepancies must be related back to the designer before commence of works this includes window specifications
- All work to be in accordance with BCA & local council by laws. ■ Do not scale off drawings, use figured dimensions
- All stormwater drains to be discharged into street gutter or registered
- drainage easement. Refer to hydraulic engineers details. All wall frames and roof trusses to be in accordance with AS1684 Framing Code .
- All timber beams to be as per engineers details and/or AS1684 framing code.
- All RC floor slab and structural beams to engineers details. All downpipes to be located by roof plumber or otherwise a noted
- on hydraulic engineers plans. ■ Termite protection AS3660.1 Kordon specs or similiar This drawing must be read inconjunction with all other approved
- plans / documents by other consultants related to this specific object
- Whilst every effort is made to obtain approval, the client acknowledges that we cannot guarantee approval as circumstance
- may arise which are beyond our control. Licence for the use of the documentation for statutory approvals or any form of construction remains the sole property of Distinct Innovations Pty Ltd. All designs and plans are the subject of Copyright Laws and remain the sole property of Distinct Innovations Pty Ltd. You will have non exclusive right to use the designs/plans
- for the purposes of this project only. You cannot use or make copies of such documents unless approval is granted by us in writing. In the event that you breach any obligation to make a payment to us, a notice of termination of agreement will be issued noting that approval to use all designs, plans and documentation has been revoked. If such is to occur, all documents, plans and designs and all copies thereof must be returned to us writing in 14 days of the date of issue of the notice of termination.
- We take no responsibility for the details or specifications in the plans/documentation of consultants that have been engaged in respect of this project. It is the responsibility of the superintendent's to check and verify all details prior to construction to satisfy him or herself that work can be carried out as required. Any discrepancies of works or directly to thr consultant who prepared the details. Distinct Innovations Pty Ltd at no time purports to be quantity sur-
- veyors for the purposes of estimating construction costs and meeting budgets. Although we can provide you with a ballpark guide to costs, we cannot formally advise you of actual costs of construction. This must only be done by a suitably qualified quantity surveyor or builder. Any opinion is expressed or otherwise given infomally and is not to be taken as a construction cost or quotation. ■ Distinct Innovations Pty Ltd expressly takes no responsibility for the
- estimates, quotes or workmanship provided to you by any consultants, building/construction companies or any other firm or person Prior to proceeding with Distinct Innovations Pty Ltd, it is your expressed responsibility to satisfy yourself that all services are available to the site for the sole purpose of this developments. Contact your relevant government bodies in relation to all services and utilities to ensure that this development can be fulfilled in every aspect. Distinct Innovations Pty Ltd will take no responsibility for inaccessible services to the development site.
- Before building works commence it is the superintendent's responsibility to ensure final architectural plans are read in conjunction with all associated plans and documents provided by other consultants and covenants related to this project. Distinct Innovations Ptv Ltd takes no responsibility for errors or omissions in this regard.
- Prior to excavation you must call Dial before you Dig.
- All work safety procedures must be conducted in the proper manner as per the new legislation WHS act 2011.



trees to be removed

tree legend



## area calculations cita araa 2394m2

site area	2386m2
proposed new dwelling	
living	308.00m2
alfresco/patio	77.00m2
garage	42.00m2
total area	427.00m2 45.96squares
landscaping	1886.00m2 or 79%
private open space	1400.00m2
site coverage	261.00m2 or 11%
floor area	350.00m2




RENOVATORS, OPERATORS, MAINTENORS AND DEMOLISHERS

THESE NOTES MUST BE READ AND UNDERSTOOD BY ALL INVOLVED IN THE PROJECT.


THIS INCLUDES (but is not excluded to): OWNER, BUILDER, SUB-CONTRACTORS, CONSULTANTS,.

amendments client / project: amendments p: 02 8850 6156 proposed new dwelling w: distinctinnovations.com.au c/o boronia building no.38b malton road beecroft nsw e: email@distinctinnovations.com.au


development application











NAS				PROJECT LOCATION  LOT 2 DP1226564  388 MALTON ROAD, BEECROFT		SHADOW DIAGRAMS	FIGURED DIMENSIONS TO BE TAKEN IN PREFERENCE TO SCALED READINGS. VERIFY ALL DIMENSIONS ON SITE.	
NY Project Services Pty Ltd				DRAWN BY YH	DATE PLOTTED 19/08/2020	SCRIPT FILE/S N/A	PROPOSED TWO STOREY	SCALE 1:400
Mob: 0403 280 297 111 Barnier Drive, Quakers Hill, NSW 2763	A REV.	19/08/2020 DATE	DA ISSUE  DESCRIPTION	CAD REFERENCE	CAD REFERENCE		DWELLING	DRAWING No. REV